
- 1. C.D.'S ARE TO BE CONSTRUCTED WITH WYES OR SANITARY "T"S (SWEEPS). STRAIGHT "T"S ARE NOT PERMITTED.
- 2. ALLOWABLE GRADES ARE 2% (1/4"/FT) MINIMUM TO 100% (FT/FT) MAXIMUM.
- 3. SEWER MUST BE STRAIGHT BETWEEN ANGLE POINTS, CHANGES IN LINE OR GRADE SHALL BE MADE WITH APPROVED FITTINGS.
- 4. NORMALLY ONLY ONE(1) CONNECTION TO THE SEWER MAIN PER BLDG. IS ALLOWED. TWO (2) DIFFERENT LAYOUTS ARE SHOWN FOR CLARITY ONLY!
- 5. NO ANGLE POINTS GREATER THAN 45° ALLOWED.
- 6. CLEAN DUTS REQUIRED PER THE UNIFORM PLUMBING CODE.
- 7. ALL SIDE SEWER PIPE SHALL BE PVC (SDR35 WITH RUBBER GASKETED JOINTS). COUPLERS PER CITY APPROVAL.
- 8. MAXIMUM CLEAN-DUT SPACING IS 100 FEET IN STRAIGHT PIPE SECTIONS.
- 9. TRENCH SAFETY SHALL BE PROVIDED PER LOCAL, FEDERAL AND STATE REGULATIONS.
- 10. CONNECTION TO SEWER MAIN PER STD DWG 6-2.
- 11. INSTALL 6" MINIMUM PIPE SIZE IN ROW.
- 12. INSTALL 6" CO PER STD PLAN 6-3.
- 13. PRIVATE SIDE SEWER 4" MINIMUM FOR SINGLE FAMILY, 6" MINIMUM FOR ALL OTHER USES.
- 14. ALL C.D.'S ON PRIVATE PROPERTY ARE TO BE ADJUSTED TO GRADE PER STD. PLAN 6-3 IF IN PAVED AREAS.



5' MAXIMUM IF GREATER



TYPICAL SIDE SEWER LAYOUTS

I:\Standard Plans

DRAWING NUMBER	STD6-1
SCALE	NONE
REVISION DATE	04/13
DEPARTMENT	PW